

Specs for Concrete Sidewalks

Site firing range must be prepped

#4 rebar around outer edge where it meets grass line

Cut approximately 56ft to square rough edges of existing concrete slab

Tear out/remove approximately 108 square feet of concrete slab

Pour approximately 3100 square feet of concrete, 4" thick, with 4000 lb fiber

All labor, materials, equipment, and waste removal to install concrete sidewalks must be furnished by vendor